

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24849-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 26-17S-14W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BEN TEMPERO Well #: A 3
County: BARTON Total Vertical Depth: 3365 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	850		

#109 36

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/24/2005 1:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY Company: TENGASCO, INC. Phone: (865) 523-1124

Proposed Plugging Method: Ordered 225 sxs 60/40 pomix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: NONE
Date/Time Plugging Completed: 09/24/2005 2:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

Arbuckle plug at 3350'.
1st. Plug at 1075' w/25 sxs.
2nd. Plug at 900' w/50 sxs.
3rd. Plug at 350' w/50 sxs.
4th. Plug at 40' w/50 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

RECEIVED

OCT 13 2005

KCC WICHITA

INVOICED

DATE

10-13-05

INV. NO

2006060616

Form CP-2/3

OCT 07 2005