

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00737-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 13-9S-23W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LAW OWWO Well #: 4-13
County: GRAHAM Total Vertical Depth: 3925 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2110 S. GILPIN PO BOX 101234
DENVER, CO 30250

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| PROD | 4.5 | 3924 | 0 | w/175 sxs cmt |
| SURF | 8.625 | 146 | 0 | w/150 sxs cmt |

\$12756

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2005 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed Plugging Method: Ordered 200 sxs cement and 675# hulls.
Perforate at 1175' and 1975'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2005 4:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2500' - circulated with 110 sxs cement and 300# hulls.
Pulled tubing - squeezed 90 sxs cement with 75# hulls.
Max. P.S.I. 300#. S.I.P. 300#.
Tied to 4 1/2" casing - squeezed 100 sxs cement with 225# hulls.
Max. P.S.I. 400#. S.I.P. 300#.
Total of 300 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 0 | 0 | | |

Remarks: SWIFT SERVICES, INC.-CEMENT. J&M TANK & ATS TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger A. Moses

RECEIVED (TECHNICIAN)

OCT 13 2005

KCC WICHITA

INVOICED

DATE

10-13-05

INV. NO

2006060618

OCT 11 2005

DON E PRATT: #4-13 LAW "OWWO" 13-9-23W
P.O. BOX 370 SW SW NW
HAYS, KS 67601

CONTR MURFIN DRILLING CTY GRAHAM

GEOL _____ FIELD MARSHALL LAW EXT (1/8 N;

E 2348 RB CM 1/8/80 CARD ISSUED 4/3/80 IP 1/4 FROM PROD
P 22 BOPD
LKC 3806-28 0A

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

NOT ASSIGNED

| API | TOPS | DEPTH | DATUM |
|-----|------|-------|-------|
| | TOP | 3389 | -1041 |
| | HEEB | 3616 | -1268 |
| | TOR | 3640 | -1292 |
| | LANS | 3653 | -1305 |
| | B/KC | 3872 | -1524 |
| | TD | 3900 | -1552 |
| | ODTD | 3925 | -1577 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

OLD INFO: OPERATOR WAS SUNRAY OIL,
#1 LAW, SPD NA, SET 8" 140, COMPLETED
AS D&A, 9/16/55

DST (1) 3772-92/1HR, 8' MUD BHP 100#
DST (2) 3798-3830/70", 30' OCM, 140'
V H OCM, BHP 1275#

NEW INFO: RE-ENTERED 1/?/80, WSH DWN
TO OTD, OD 3925' TD, SET 4" 3924,
MICT - CO, PF (LKC) 3822-28, 3806-12,
SWB DWN, NS, NAT, AC 500, SWB 1.16
BFPH (43% O), AC 1500, SWB 1.16 BFPH,
(56% O), POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS