

3 022800

15-00101998 00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 1:00P.M. Day: 27 Month: 7 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 4 1/2" CASING TO 865' THAT HAD BEENCEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TOCIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All X Part _____

TECHNICIAN

None _____

Operations Completed: Hour: 5:00P.M. Day: 27 Month: 7 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 850'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.140 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.5) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP)(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

OCT 17 2005

KCC WICHITA

RECEIVED

AUG 12 2005

KCC WICHITA