

3 022812

15.001.01994.0000

To:

STATE CORPORATION COMMISSION

NE, NW, SE API NUMBER
SE SW NE 1/4

CONTROL NO. 20050040-017

Sec/Twp/Rge S.21-T.25S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

2506 feet from south section line

130 S. Market, Room 2078

1657 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# DOTY NO.03

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 750' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850'

Address

Surface Casing: 12" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 11:00A.M. Day: 5 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT

HAD BEEN CEMENTED IN FROM T.D. TO 290'. THE PLUGGING PROPOSAL WAS

TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE

AND OUTSIDE THE 2" CASING.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

X

TECHNICIAN

None

Operations Completed: Hour:

2:00P.M.

Day:

4 Month:

8

2005

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 12"

ANNULUS TO 290'. AT THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2"

AND 12" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 230 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.17) (THIS WELL WAS NO.3 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

RECEIVED

OCT 17 2005

KCC WICHITA

RECEIVED

AUG 17 2005

KCC WICHITA

Signed:

Clayton P. Titel
TECHNICIAN

Bm