

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21338-00-00
Spot: NESW Sec/Twnshp/Rge: 8-31S-18W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: THOMPSON Well #: 2-8
County: COMANCHE Total Vertical Depth: 5197 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: 155 N. MARKET - SUITE 800 PO BOX 4
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4900		WITH 2 SX CMT
CIBP		5030		
PROD	4.5	5197	2500	WITH 250 SX CMT
SURF	10.75	305		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2005 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4900' WITH 2 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 340' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2005 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SET CIBP @ 4900' WITH 2 SX CMT. 1ST PLUG AT 1128' WITH 15 SX GEL & 50 SX CMT. NO CIRCULATION. WAIT 2 1/2 HOURS. RAN WIRELINE TOC @ 934'. 2ND PLUG PULL TO 600'. PUMP 65 BBLs WATER. NO CIRCULATION. PUMP 50 SX CMT AT 600'. SDON. 3RD PLUG TAG CMT @ 532'. PARTIAL CIRCULATION. RAN GEL & HULLS WITH 50 SX CMT. PLUG HELD. 4TH PLUG PULL TO 325'. PUMP 75 SX CMT. GOOD CIRCULATION. 5TH PLUG PULL TO 40'. PUMP 20 SX CMT TO SURFACE. GOOD CIRCULATION.

Perfs:


Top	Bot	Thru	Comments
5098	5102		
5042	5046		
4940	4944		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

INVOICED
DATE 10-18-05
INV. NO. 2006060633

District: 01



Signed

Jerry W. Stapleton PART II
(TECHNICIAN)

RECEIVED

OCT 17 2005

KCC WICHITA

Form CP-2/