

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01667-00-00
Spot: E2SENW Sec/Twnshp/Rge: 5-18S-10W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: VOLKLAND W F Well #: 9-B
County: RICE Total Vertical Depth: 3218 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3214		100 SX CMT
SURF	8.625	203		85 SX CMT

104⁵⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2005 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed Plugging Method: Set CIBP 50' above perms or OH & cap with 2-4 sxs cement. Perf @ 1250', 850' & 260'. Run tubing to 1250' and pump 35 sxs cement; pull tubing to 850' and pump 35 sxs; and pull tubing to 260' and circ cement to surf.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE
Date/Time Plugging Completed: 09/21/2005 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Obstructions encountered at 1100' and 1700'. Ran tubing and bit with power swivel down to 2722'; hit iron. Pumped 25 sacks of cement and perforated at 1250', 850', and 260'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 260' and circulated cement to surface.

60/40 posmix with 4% gel

Swift #8696

Perfs:

Top	Bot	Thru	Comments
3214	3218		

**RECEIVED
KCC DISTRICT #2
OCT 3 - 2005
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED
DATE 10-19-05
INV. NO 2006060639

**RECEIVED
OCT 19 2005
KCC WICHITA**

Form CP-2/3