

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01985-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 32-18S-9W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: VOLKLAND Well #: 8
County: RICE Total Vertical Depth: 3230 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3225		100 SX CMT
SURF	8.625	210		85 SX CMT

98
\$104

Well Type: OIL UIC Docket No.: _____ Date/Time to Plug: 09/19/2005 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed Plugging Method: Set CIBP 50' above perfs or OH and cap with 5 sx cement. Perf at 1250', 850', and 260'. Run tubing to 1250' and pump 35 sx cement; pull tubing to 850' and pump 35 sx cement; and pull tubing to 260' and circ cement to surf.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2005 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Set CIBP @ 3200' and capped with 4 sacks of cement. Perforated at 1250', 850', and 260'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 260' and circulated cement to surface. Circulated cement on backside of 5-1/2" at 200 lbs.

60/40 posmix with 4% gel

Swift Services #8693

Perfs:

Top	Bot	Thru	Comments
3225	3230		

RECEIVED
KCC DISTRICT #2
SEP 26 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 10-19-05
INV. NO. 2006060639

RECEIVED
OCT 19 2005
KCC WICHITA

d