

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21103-00-00
Spot: SESESW Sec/Twnshp/Rge: 30-17S-10W
330 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BECK Well #: 7
County: ELLSWORTH Total Vertical Depth: 3298 feet

Operator License No.: 7030
Op Name: EVANS, JOHN ROY
Address: BOX 385 405 FOURTH STREET
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3282		
PROD	5.5	3285		75 SACKS
SURF	8.625	342		200 SACKS

107¹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 2975'; cap with 5 sxs cement; cut off casing & pull to 1325'; pump 35 sxs & pull to 950'; pump 35 sxs & pull to 390'; and circ cement to surf.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 09/28/2005 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2975' and capped with 5 sacks of cement. Cut off casing at 2400'.
Pulled casing to 1325' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 390' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #17973

Perfs:

Top	Bot	Thru	Comments
3026	3040		

RECEIVED
KCC DISTRICT #2
OCT 10 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 10-19-05
INV. NO 2006060641

RECEIVED
OCT 19 2005
KCC WICHITA