

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20869-00-00  
Spot: N2SWSWNE Sec/Twnshp/Rge: 27-16S-10W  
3205 feet from S Section Line, 2422 feet from E Section Line  
Lease Name: MONTGOMERY Well #: 3-A  
County: ELLSWORTH Total Vertical Depth: 3321 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W. 47TH ST STE 412  
KANSAS CITY, MO 64112

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 5.5   | 3320       |             |         |
| SURF   | 8.625 | 406        |             |         |

93  
\$ 107

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2005 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 2950' and cap with 5 sxs; pump 35 sxs @ 1350'; 35 sxs @ 1000'; circ from 455' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/29/2005 3:00 PM KCC Agent: GREG EVES

**Actual Plugging Report:**

Sanded pipe at 2950' and capped with 5 sacks of cement. Cut pipe off at 1593'. Pulled pipe to 1350' and pumped 35 sacks of cement. Pulled pipe to 1000' and pumped 35 sacks of cement. Pulled pipe to 450' and pumped 210 sacks of cement and circulated to surface.

280 sxs total 60/40 posmix with 4% gel

Allied Cement #22533

Perfs:

**RECEIVED  
KCC DISTRICT #2  
OCT 4 - 2005  
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed

*Greg Eves*

(TECHNICIAN)

**INVOICED**  
DATE 10-19-05  
INV. NO. 2006060644

**RECEIVED  
OCT 19 2005  
KCC WICHITA**