

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21195-00-01

Spot: SESESW

Sec/Twnshp/Rge: 12-24S-9W

330 feet from S Section Line, 2310 feet from W Section Line

Lease Name: ANDSAGER

Well #: 1-12

County: RENO

Total Vertical Depth: 4090 feet

Operator License No.: 6723

Op Name: BAKER, DON DBA CAMIO OIL COMPA

Address: PO BOX 308
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PKR		3718		
-----	--	------	--	--

PROD	5.5	3956	2650	
------	-----	------	------	--

SURF	8.625	160		
------	-------	-----	--	--

T1	2.375	3716		
----	-------	------	--	--

93
#132

Well Type: EOR

UIC Docket No: E27389.1

Date/Time to Plug: 08/23/2005 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed
Plugging
Method:

See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/23/2005 10:30 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded to 3687' and capped with 5 sacks of cement. Cut off casing at 2650'. Pulled to 1350' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 800' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 210' and circulated cement to surface.

60/40 posmix with 4% gel

United Cement #6475

Perfs:

Top	Bot	Thru	Comments
3798	3799		
3790	3791		
3787	3788		
3780	3781		
3777	3778		
3766	3767		
3760	3761		
3757	3758		
3754	3755		

RECEIVED
KCC DISTRICT #2
AUG 23 2005
WICHITA, KS

Remarks: CAMIO OIL IS TO BE INVOICED WHEN T-1 IS APPROVED.

Plugged through: CSG

District: 02

Signed

Virgil Clothier

RECEIVED
(TECHNICIAN)

OCT 19 2005

KCC WICHITA

INVOICED

DATE

10-19-05

INV NO

2006060640