

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21735-00-00
Spot: S2SWNESE Sec/Twnshp/Rge: 34-19S-16W
1485 feet from S Section Line, 1000 feet from E Section Line
Lease Name: BLANCHE Well #: 1
County: RUSH Total Vertical Depth: 3850 feet

Operator License No.: 30337
Op Name: SPECIAL ENERGY CORP.
Address: PO BOX 369
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3849	2670	WITH 150 SX CMT
SURF	9.625	1053		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2005 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3620' & 7 SX CMT. PLUG AT 1090' WITH 20 SX GEL & 60 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2005 11:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3620' & 7 SX CMT. SPOTTED PLUGS THROUGH TUBING. 1ST PLUG AT 1090' WITH 20 SX GEL - 60 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3747	3786		
3684	3783		


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

INVOICED

DATE 10-18-05
INV. NO. 2006060636

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)
RECEIVED

OCT 17 2005

KCC WICHITA

Form CP-23