

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

CLOUD

County. Sec. 18 Twp. 7S Rge. (E) 3 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SW
Lease Owner Shawver-Armour, Inc.
Lease Name HALL Well No. 1
Office Address 817 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-30-56 19
Application for plugging filed 10-30-56 19
Application for plugging approved 10-30-56 19
Plugging commenced 10-30-56 19
Plugging completed 10-30-56 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Hilyardt
Producing formation Arbuckle Depth to top 3858 Bottom 3898 Total Depth of Well 3898 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	318	8-5/8	318	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3898 - 310 Fill w/heavy mud
310 Good permanent bridge, then 1/2 sax hulls, then 20 sax cement thru drill pipe and fill w/heavy mud to 40'
40 Good permanent plug, then 1/2 sax hulls, then Halliburton Plug and 10 sx cement to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour
817 Central Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 56

My commission expires December 29, 1959

Notary Public.

PLUGGING
FILE SEC 18 T 7 R 3W
BOOK PAGE 112 LINE 27

NOV - 7 1956
CONSERVATION DIVISION
11-7-56