


15-163-00818-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Date: 1-6-61

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 9 Twp. 7S Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines Corner SE SE NW
Lease Owner Cities Service Petroleum Company
Lease Name Oliva Well No. 1
Office Address Box 553, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-2-1960 Col
Application for plugging filed 1-2-1960 Col
Application for plugging approved 1-3-1961
Plugging commenced 1-3-1961
Plugging completed 1-3-1961
Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production --- 19---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	33 Jts 1301'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Rotary Mud 3401' to 500'
Howco Plug and 20 sx. cement at 500'
Mud to 180'
Howco Plug and 20 sx. cement to 180'
Mud to 35'
Howco Plug - 1/2 sx. hulls and 10 sx. cement
to base of cellar.
Job complete 7:00 A.M. 1-3-61

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1961
01-18-1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address Box 359 - Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

M. M. Hardin (employee of owner) or (~~owner of property~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M M Hardin

Box 553, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1961

My commission expires March 18, 1963

W. D. Smith
Notary Public.



WELL RECORD

15-163-00818-00-00

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil
Petrochem Company WELL # 1 FARM Oliva

LOCATION 2310' South and 2310' East of NW Corner
Section 9, Township 7, Range 17W.

ELEV. 1912 (1909 Gr.) CO. Rocks STATE Kansas

IP. Dry hole. P. & A. 1-3-61.

PERFS.....

FRAC..... ACID None

T.D. 3401' PBTD..... GRAV/GOR.....

DRLG. COMM..... COMP..... CONTRACTOR Pool Bros., Inc.

CASING RECORD:

8-5/8" at 1301' with 600 sacks cement.

FORMATION RECORD:

lime	0-99
shale	186
pyrite	188
shale and shells	340
shale	525
sand	560
lime and shale	660
sand and streaks pyrite	685
sand and shells	790
sand	980
shale and shells	1240
red bed	1292
Anhydrite	1322
shale and lime shells	1600
shale and shells	1770
shale and lime	1970
lime	2350
lime, shale and shells	2455
shale and lime	2700
broken lime	2765
shale	2796
lime	2960
lime and shale	3015
shale and lime	3059
lime	3062
lime and shale streaks	3092

lime	3200
lime and shale streaks	3245
lime and shale	3257
lime	3350
lime and shale	3385
lime	3401 T.D.

SLOPE TESTS (SYFO):

500'	-	1*
1000'	-	1*
1500'	-	1*
2005'	-	1*
2585'	-	1*
3100'	-	1*

7-7/8" Rotary Hole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1961

CONSERVATION DIVISION
Wichita, Kansas