

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20470-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1972

11-10-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Wilson Exploration, Inc.

Complete Address Wilson, Kansas 67490

Lease Name McDowell Well No. 1

Location NW NE NW Sec. Twp. 34 Rge. 7 (E) (W) 16

County Rooks Total Depth 3152'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 2:30 P Day 7 Month 11 Year 1972

The above well was plugged as follows:

RTD 3152' 8 5/8 csg set at 220' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 11/10/72

INV. NO. 6614-10