

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21471-00-00
Spot: S2NENW Sec/Twnshp/Rge: 2-20S-16W
990 feet from N Section Line, 1980 feet from W Section Line
Lease Name: BERNICE Well #: 1
County: PAWNEE Total Vertical Depth: 3954 feet

Operator License No.: 30337
Op Name: SPECIAL ENERGY CORP.
Address: PO BOX 369
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3850	2890	WITH 200 SX CMT
SURF	9.625	1030		WITH 425 SX CMT #128 51

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2005 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3596' & 7 SX CMT. PLUG AT 1060' WITH 38 SX GEL & 60 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2005 11:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3596' & 7 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 1060' WITH 38 SX GEL & 60 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3760	3774		
3700	3750		
3688	3694		
3674	3678		
3662	3668		

RECEIVED
OCT 07 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 10-7-05
INV. NO. 2006060599

Form 10/23