

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-21,899 -00-00

LEASE NAME Lowry H-9

WELL NUMBER # 1

320 Ft. from S Section Line

1640 Ft. from ~~X~~<sup>W</sup> Section Line

SEC. 18 TWP. 7s RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-6-89

Plugging Completed 7-6-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Lawbanco Drilling, Inc.

ADDRESS P. O. Box 289 Natoma, Kansas 67651

PHONE# (913) 885-4676 OPERATORS LICENSE NO. 5900

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-19-89 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes *sent log with plugging request*

Producing Formation Arbuckle Depth to Top 3301 Bottom 3305 T.D. 3342

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content     | From | To   | Size  | Put In | Pulled out |
|-----------|-------------|------|------|-------|--------|------------|
| Arbuckle  | oil & water | 3313 | 3316 | 5 1/2 | 3342'  | none       |
|           |             | 3301 | 3305 | 8 5/8 | 1230'  | none       |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
 Pump down 8 5/8 csg, 150 sacks 65/35 poz 8% gel with 150 # hulls max 900 close 350 psi.  
 Pump down 5 1/2 csg 100 sacks 65/35 poz 8 % gel with 150# hulls max 1800 close 1000psi.  
 Pump down 8 5/8 csg 100 sacks 65/35 poz 8% gel 100# hulls max 900 close 600 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co, Inc. License No. \_\_\_\_\_

Address P. O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lawbanco Drilling, Inc.

STATE OF Kansas COUNTY OF Osborne, ss.

E. L. Miller (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E. L. Miller

(Address) P. O. Box 194 Victoria, Ks. 67671



SUBSCRIBED AND SWORN TO before me this 18th day of July, 1989

Reva F. Musgrove  
 Notary Public

My Commission Expires: 3-28-92

