

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-21886-00-00

API NUMBER 15-NA

LEASE NAME M. Rogers

WELL NUMBER No. 1

330' Ft. from (S) Section Line

1650' Ft. from (E) Section Line

SEC. 18 TWP. 7S RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed 11/30/82

09:00

Plugging Commenced 8/26/93

11:00

Plugging Completed 8/26/93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR American Lariat

ADDRESS 250-6th Ave. SW, Calgary Alberta, Canada T2P 3G6

PHONE# (403)-266-1024 OPERATORS LICENSE NO. 6656

Character of Well Oil

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/18/93 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3295' Bottom N.R. T.D. 3319'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand		0	110'	13 3/8"	105'	0
Anhydrite		0	1232'	8 5/8"	1228'	0
Arbuckle		0	3322'	5 1/2"	3322'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

C.I. BP @ 3280' C.I. BP @ 3268' 1 sack cement on plug.

Dug out cellar, found good cement between 13 3/8 and 8 5/8 casing.

Cement down annulus 8 5/8 & 5 1/2" displace 15 Sx, pressure to 500#, change to 5 1/2" Csg.

Pump 25 Sx, followed W/5 Halls and 185 Sx, 60/40 Poz, 10% Gel, 1/4# Flo-seal /Sx.
 (If additional description is necessary, use BACK of this form.)

Hole full pressure to 600# shut in @ 300#

Name of Plugging Contractor Allied Cementing Co. License No. N.A.

Address Hays Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Lariat Calgary Alberta, Ca.


STATE OF Kansas COUNTY OF Rooks, ss.

Charles D. Farr (Engineering Consultant) (Employee of Operator) or (Operator) of above-described well, being first duly sworn before me, says: That I have knowledge of the facts, statements, and matters herein stated and the log of the above-described well as filed that the same are true and correct, so help me God.

AUG 30 1993
 08-30-1993

Signature: Charles D. Farr

(Address) Hays, Ks. 67601



My Comm. Expires: 7-2-95

AND SWORN TO before me this 27th day of August, 19 93

Nancy Taggart
 Notary Public

My Commission Expires: 7-2-95

Phone 913-483-2627, Russell, Kansas

Phone Plainville 913-434-2812

Phone 316-793-5861, Great Bend, Kansas

15-163-21886 00-00

Phone Ness City 913-798-3843

ALLIED CEMENTING CO., INC.

4538

Home Office P. O. Box 31

Russell, Kansas 67665

Date	8-26-93	Sec.	18	Twp.	7.5	Range	17W	Called Out	8:00 AM	On Location	9:00 AM	Job Start	9:30 AM	Finish	1:00	
Lease	M. Rodgers	Well No.	1	Location				East Edge of Stockton	County	Rock	State	KS				

Contractor		Owner	
Type Job		To Allied Cementing Co., Inc.	
Hole Size		You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Csg.		Charge To	
Tbg. Size		Street	
Drill Pipe		City	
Tool		State	
Cement Left in Csg.		The above was done to satisfaction and supervision of owner agent or contractor.	
Press Max.		Purchase Order No.	
Meas Line		Cement	
Perf.		Amount Ordered	

Type Job		Plug to Abandon	
Hole Size		7 1/8	
Csg.		5 1/2	
Tbg. Size			
Drill Pipe			
Tool			
Cement Left in Csg.		Shoe Joint	
Press Max.		Minimum	
Meas Line		Displace	
Perf.			

EQUIPMENT

No.	Cementer	Helper
Pumptrk 153	Dave	Mark
No.	Cementer	Helper
Pumptrk		
No.	Driver	
Bulktrk 283	Wayne	
No.	Driver	
Bulktrk		

Amount Ordered	250.00	49.40	102.00	19.40	41.20	1.00
Consisting of	used 225					
Common	175.00	35.00				716.00
Poz. Mix	70.00	3.00				270.00
Gel.	19.00	2.00				153.00
Chloride	48.00	11.00				52.00
Quickset	5.00	14.00				70.00
Handling	1.00	Per sk				250.00
Mileage	4.00	Per mile				140.00
Sub Total	2133.50					
Tax	426.20					
Total	2559.70					

DEPTH of Job		Reference:	
		Pump-trk	410.00
		222 Per mile	31.50
		14 miles	
Sub Total			
Tax			
Total			441.50

Handling	1.00	Per sk	250.00
Mileage	4.00	Per mile	140.00
Sub Total	2133.50		
Tax	426.20		
Total	2559.70		
RECEIVED 706.00			
STATE COMMISSION			
AUG 30 1993			

Remarks:
 Pump 15 sks down back side of casing 400' max 30' shut-in

CONSERVATION DIVISION
 Wichita, Kansas
 AUG 30 1993
 RECEIVED 706.00
 STATE COMMISSION