

15-163-19074-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail Deliver Report to:
Conservation Division
State Corporation Commission
No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 33 Twp. 7 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner Robin Oil Corporation

Lease Name Stamback Well No. 1

Office Address Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5-28-65 19

Plugging completed 6-2-65 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3367 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	None
				5-1/2"	3363'	2722'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3367', sanded to 3350' and dumped 4 sacks of cement @ 3350' with dump bailer. Pulled 5 1/2" casing to 600' and circulated with 27 sacks of gel mud. Pumped in 20 sacks of cement @ 600'. Pulled 5 1/2" casing to 180' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of June 1965

My commission expires May 20, 1968 Milton J. Volin Notary Public