

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out Completely
and return to cons. div.
office within 30 days.

API NUMBER 15-163-21,118 20-00
LEASE NAME Schruben
WELL NUMBER 1
1650 N ft. from S Section Line
330 W ft. from E Section Line
SEC. 29 TWP. 7 RGE. 17 (E) or (W)
COUNTY Rooks
Date Well Completed _____
Plugging Commenced 12/6/02
Plugging Completed 12/9/02

LEASE OPERATOR Black Diamond Oil, Inc.
ADDEESS PO Box 641, Hays, KS 67601
PHONE # (785) 625-5891 OPERATORS LICENSE NO. 7076
Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 12/6/02 (date)
by Herb Deines (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? Sent with application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3317
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1228	none
				5 1/2	3315	1806

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand bottom, ran 5 sacks cement. Shot pipe t 2209', 1806, came free. Pull to 1700', pump 100 sacks cement, 3 sacks hulls. Pull to 1300', pump 40 sacks cement, 1 sack hulls, pull to 700', pump 30 sacks cement. Pull to 250', circulate cement to surface

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641

SUBSCRIBED AND SWORN TO before me 28th day of February, 2003

KCC WICHITA

[Signature]
Notary Public Verda M. Brin



[Signature]

ALLIED CEMENTING CO., INC. 11498

Federal Tax I.D. [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

15-163-21118-00-00

DATE <u>12/9/02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>12:00p.m.</u>	JOB START	JOB FINISH <u>2:15p.m.</u>
LEASE <u>Schreiben</u>	WELL# <u>I</u>	LOCATION <u>Stockton 13 1E 12S</u>			COUNTY <u>Rooks</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)				<u>Ed 5 Juto</u>			

CONTRACTOR <u>Quality</u>	OWNER
TYPE OF JOB <u>OHF</u>	
HOLE SIZE <u>7 7/8</u>	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT	
AMOUNT ORDERED <u>225 60/40 1090 Gel</u>	
<u>4 Halls</u>	
<u>USED 200sx 4 Halls</u>	

COMMON	<u>120</u>	@	<u>665</u>	<u>798⁰⁰</u>
POZMIX	<u>80</u>	@	<u>355</u>	<u>284⁰⁰</u>
GEL	<u>14</u>	@	<u>10⁰⁰</u>	<u>140⁰⁰</u>
CHLORIDE		@		
<u>Halls</u>	<u>4</u>	@	<u>18⁰⁰</u>	<u>72⁰⁰</u>
		@		
		@		
		@		
		@		
HANDLING	<u>225</u>	@	<u>110</u>	<u>247⁵⁰</u>
MILEAGE	<u>44 1/2</u>	@	<u>mile</u>	<u>360⁰⁰</u>
TOTAL				<u>1901⁵⁰</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Paul</u>
# <u>177</u>	HELPER <u>Darin</u>
BULK TRUCK	
# <u>362</u>	DRIVER
BULK TRUCK	
#	DRIVER

REMARKS:

1750 - 100sx 3 Halls
1400 - 40sx 1 Hall
700 - 30sx
250 - Circ Cement w/ 30 sx

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>475⁰⁰</u>
EXTRA FOOTAGE	@
MILEAGE <u>40</u>	@ <u>3⁰⁰</u> <u>120⁰⁰</u>
PLUG	@
	@
	@
TOTAL <u>595⁰⁰</u>	

CHARGE TO: Black Diamond
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@
	@
	@
	@
	@

RECEIVED

MAR 11 2003

KCC WICHITA

To Allied Cementing Co., Inc.