

RECEIVED

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

SEP 27 2005

Form CP-1 September 2003

WELL PLUGGING APPLICATION KCC WICHITA

This Form must be Typed Form must be Signed All blanks must be Filled

Please TYPE Form and File ONE Copy

API # 15 - 051-20,544 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 4/2/70

Well Operator: The Bill Bowman Oil Company (Owner / Company Name) KCC License #: 33263 (Operator's)

Address: 2640 W Road City: Natoma

State: Kansas Zip Code: 67651 Contact Phone: (785) 885 - 4830

Lease: Jacobs-Peavey Well #: 2 Sec. 26 Twp. 11 S. R. 18 East West

SE NE SW Spot Location / QQQQ County: Ellis

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well SWD Docket # ENHR Docket # Other:

Conductor Casing Size: None Set at: Cemented with: Sacks

Surface Casing Size: 8 5/8 Set at: 200 Cemented with: 175 Sacks

Production Casing Size: 5 1/2 Set at: 3700 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3365-68, 3372-74, 3396-3401, 3435-37, 3441-43, 3450-53, 3525-30, 3543-47, 3614-17.

Elevation: 2109 (G.L./K.B.) T.D.: 3700 PBDT: Anhydrite Depth: 1367-1409

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): The well will be plugged according to KCC rules and regulations.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why?

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: William F. Bowman

Phone: (785) 885 - 4830

Address: 2640 W Road City / State: Natoma, Kansas

Plugging Contractor: Swift Cementing (Company Name) KCC License #: (Contractor's)

Address: P.O. Box 466 Ness City, Kansas 67560 Phone: (785) 798-2300

Proposed Date and Hour of Plugging (if known?): 10:00 a.m. September 09, 2005 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: Sept. 06, 2005 Authorized Operator / Agent: William F. Bowman (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

4/06

10/05

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20544-00-00
Spot: SENESW Sec/Twnshp/Rge: 26-11S-18W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JACOBS-PEAVEY Well #: 2
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W ROAD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3700	0	w/150 sxs cmt
SURF	8.625	200	0	w/175 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2005 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BILL BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 885-4830

Proposed Plugging Method: Ordered 300 sxs cement and 750# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2005 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran 1" tubing to 1165' - spotted 25 sxs cement.
Pulled 1" and ran 2 3/8" tubing to 795' - circulated with 140 sxs cement and 700# hulls.
Pulled all 2 3/8" tubing - squeezed 5 1/2" w/70 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.
Tied to 8 5/8" S.P. and squeezed with 35 sxs cement and 50# hulls.
Max. P.S.I. 250#. S.I.P. 250#.
Total of 270 sxs 60/40 pozmix - 10% gel - 750# hulls.

Remarks: SWIFT SERVICES, INC. BOWMAN OIL-RIG. KELLER TANK & BOWMAN TANK-WATER

Plugged through: TBG

District: 04

Signed

Roger L Moses
(TECHNICIAN)

RECEIVED
SEP 27 2005
KCC WICHITA

SEP 15 2005



P. O. Box 466
Ness City, KS 67560
Off: 785-798-2300



Invoice

DATE	INVOICE #
9/9/2005	8713

BILL TO
Bowman Oil Company 805 Codell Road Codell, KS 67663-8500

- Acidizing
- Cement
- Tool Rental

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#2	Jacobs-Peevey	Ellis	Bowman Well Ser...	Oil	Workover	PTA	Dave
PRICE REF.	DESCRIPTION				QTY	UM	UNIT PRICE	AMOUNT
575W	Mileage - 1 Way				40	Miles	4.00	160.00T
576W-P	Pump Charge - PTA				1	Job	650.00	650.00T
275	Cotton Seed Hulls				10	Sack(s)	28.00	280.00T
330	Swift Multi-Density Standard (MIDCON II)				270	Sacks	11.00	2,970.00T
581W	Service Charge Cement				300	Sacks	1.10	330.00T
583W	Drayage				597.6	Ton Miles	1.00	597.60T
	Subtotal							4,987.60
	Sales Tax Ellis County						5.30%	264.34
We Appreciate Your Business!							Total	\$5,251.94

RECEIVED
SEP 27 2005
KCC WICHITA

JOB LOG

SWIFT Services, Inc.

DATE 0909-05 PAGE NO. 1

CUSTOMER Bowman O. Co WELL NO. #2 LEASE Jacobs-Recovery JOB TYPE P.T.A. TICKET NO. 8713

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1000							ONLOCATION, Dress Job, Setup, 300SG SMO CMT 1000' Hubs 5 1/2" CSG 3700, 2 3/8" Tgs 900' to 3670, Rods 1000' to 3670 1" Tgs 1165' to CMT thru.
	1050	1.0	.1	✓		875		Pump H2O thru 1"
	1052	1.0	2.0	✓		800		
	1052	1.0	0	✓		800		Start Mixing CMT 255SG CMT
		1.1	4.0	✓		1150		
		1.2	8.0	✓		1300		
	1105	1.2	14.0	✓		1300		end CMT
		1.2	15.0	✓		1300		Pump 1 bbl H2O to clean 1" Tgs Pull 1" Tgs out, Run in 2 3/8" Tgs
	1215		0	✓		0	0	Hookup to 8 5/8" 1 bag Hubs 75' 255SG CMT
			8	✓			0	
	1225	4.0	0	✓		100		Hookup to 2 3/8" Tgs @ 795' FT
		4.0	7	✓		150		Start to Circ Oil out Ann. Start Hubs
		4.0	45	✓		200		Circ. CMT end Hubs 675'
		4.0	47	✓		200		end CMT 140SGS CMT
								Pull 2 3/8" Tgs out
	1320	2.0	0	✓		0	0	Pumpdown 5 1/2" CSG
			6	✓		300		Close in 205SGS CMT
	1330		0	✓		0	0	Hookup to 8 5/8"
			4	✓		250		105SGS CMT
	1335	1.0	0	✓		0	0	Hookup to 5 1/2"
		1.0	2.0	✓		200		
		1.0	15.0	✓		300		50SGS
								Washup
								Reckup
								Tickets
	1430							Job Complete

Thank You!
Dave, Blake, Rob

RECEIVED
SEP 27 2005
KCC WICHITA



ADDRESS Bowman Oil Co
 CITY, STATE, ZIP CODE

No 8713

PAGE 1 OF 1

SERVICE LOCATIONS 1. HKS KS WELL/PROJECT NO. #2 LEASE Jacobs-Deavey COUNTY/PARISH Ellis STATE KS CITY DATE 09-09-05 OWNER
 2. Ness City KS TICKET TYPE SERVICE CONTRACTOR Bowman Well Serv. RIG NAME/NO. SHIPPED VIA C.T. DELIVERED TO 16 1/2 into River Rd ORDER NO.
 3. WELL TYPE Oil WELL CATEGORY Abandon JOB PURPOSE P.T.A. WELL PERMIT NO. WELL LOCATION
 4. REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE #105	40	mi			4.00	160.00
576P		1			Pump Service	1	hrs			650.00	650.00
275		1			Cotton Seed H-1/4	10	S/4			28.00	280.00
.330		2			SMD Comment	270	S/4			11.00	2970.00
581		2			Service Chg CMT	300	S/4			1.10	330.00
583		2			Drayage	5976	Tm			1.00	5976.00

RECEIVED
 SEP 27 2005
 KCC WICHITA

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X Bobby L. Hays
 DATE SIGNED 09-09-05 TIME SIGNED 1000
 A.M.
 P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				4,987.60
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				Ellis TAX 5.3% 264.30
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL 5251.90
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR DAVEAH APPROVAL

Thank You