

OCT 18 2005

CONSERVATION DIVISION  
WICHITA, KSKANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE CopyForm CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be FilledAPI # 15 - 035-02123 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 4-10-1957 4/06Well Operator: W.D. Short Oil Co., LLC KCC License #: 33608  
(Owner / Company Name) (Operator's)  
Address: PO Box 729 - 102 S. River Road City: Oxford  
State: Kansas Zip Code: 67119 Contact Phone: ( 620 ) 455 - 3576  
Lease: Hart Well #: 2 Sec. 2 Twp. 34S S. R. 5 ☒ East ☐ West  
C - SE - NE - SE Spot Location / QQQQ County: Cowley1650' Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)  
330' Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)Check One: ☒ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well  
☐ SWD Docket # \_\_\_\_\_ ☐ ENHR Docket # \_\_\_\_\_ ☐ Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 97' Cemented with: 90 SacksProduction Casing Size: 4 1/2" Set at: 3099' Cemented with: 125 SacksList (ALL) Perforations and Bridgeplug Sets: 3097-3118 (OH)Elevation: 1241 (☐ G.L. / ☒ K.B.) T.D.: 3118 PBDT: \_\_\_\_\_ Anhydrite Depth: 505'  
(Stone Corral Formation)Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in HoleProposed Method of Plugging (attach a separate page if additional space is needed): Per KCC Rules & Regs.Is Well Log attached to this application as required? ☒ Yes ☐ No Is ACO-1 filed? ☒ Yes ☐ No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike AnstinePhone: ( 620 ) 218 - 1822Address: PO Box 729 - 102 S. River Road City / State: Oxford, Kansas 67119Plugging Contractor: B. P.C. Well Plugging KCC License #: 32475  
(Company Name) (Contractor's)Address: PO Box 282 - Burden, KS 67019 Phone: ( 620 ) 438 - 2856Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-18-05 Authorized Operator / Agent: W.D. Short Resident Agent  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WELL F-1 Hart #2

DRILLERS' LOG

SUN OIL COMPANY  
Hart No. 2  
SE/4 NE/4 SE/4  
Sec. 2, Twp. 34S, Rge. 5E  
Cowley County, Kansas

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 18 2005  
CONSERVATION DIVISION  
WICHITA, KS

FORMATION	FROM	TO
Shaly lime	0	505
Limey shale	505	1148
Lime w/shale strks	1148	1231
Limey shale	1231	1330
Sand w/strks shale	1330	1462
Shale & lmy. shale	1462	1608
Lime	1608	1625
Shale & lmy. shale	1625	1921
Shale	1921	2093
Lime	2093	2130
Shale	2130	2339
Sand (Layton)	2339	2442
Shale	2442	2474
Lime (Kansas City)	2474	2588
Shale	2588	2613
Limey shale	2613	2720
Lime	2720	2853
Shale & lmy shale	2853	3097
Chat (Miss.) (oil)	3097	3116
Lime (Miss.)	3116	3118
		T.D.

Drilling Commenced 3-22-57  
Drilling Completed 4-3-57

CASING RECORD:

8-5/8" set at 97.09', cemented 90 sax  
4 1/2" set at 3099', cemented 125 sax.

I hereby certify that the foregoing is a true and correct copy of the Hart No. 2 well log as recorded on the books of Sun Oil Company, Tulsa Oklahoma

J. H. Allen  
J. H. Allen

STATE OF OKLAHOMA )  
COUNTY OF TULSA ) SS

Subscribed and sworn to before me this 19 day of April, 1957.

Bauche Fork  
Notary Public

My Commission Expires:

May 9, 1959

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. Short Oil Co., LLC  
PO Box 729 - 102 S. River Road  
Oxford, KS 67119

October 21, 2005

Re: HART #2  
API 15-035-02123-00-00  
SENESE 2-34S-5E, 1650 FSL 330 FEL  
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000