

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24628-00-00  
Spot: N2S2NW Sec/Twnshp/Rge: 17-20S-11W  
3630 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: CAROL Well #: 1  
County: BARTON Total Vertical Depth: 3292 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: RR 1 BOX 183B 7 SW 26TH AVENUE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3290	0	150 SX CMT
SURF	8.625	334	0	250 SX CMT

99  
\$ 106

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2005 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2005 10:30 AM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Kelso sanded off bottom perfs to 3000' and topped with 5 sxs cement using a dump bailer.  
Cut casing at 2490' - pulled to 1325'.  
Copeland tied onto casing - pumped 95 sxs cement with 300# hulls mixed in.  
Pulled casing to 550' - pumped 40 sxs cement with 100# hulls mixed in.  
Pulled casing to 200' - pumped 125 sxs cement to circulate cement to surface.  
POOH. Hole standing full.  
Well had various lengths of casing pulled.  
Original cement order was 190 sxs.

**Perfs:**

Top	Bot	Thru	Comments
3274	3278		
3186	3192		
3074	3078		
3052	3060		

Remarks: COPELAND CEMENTING & ACID COMPANY-TICKET #26307.

Plugged through: CSG

District: 04

Signed [Signature]  
(TECHNICIAN)

**INVOICED**

DATE 10-26-05  
INV NO 2006060675

**RECEIVED**

**OCT 26 2005**

**KCC WICHITA**

Form CP-2/3

**OCT 20 2005**

