

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03096-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 2-14S-20W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: ORTH Well #: 3  
County: ELLIS Total Vertical Depth: 3876 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3861	0	150 SX CMT
SURF	8.625	1555	0	400 SX CMT

#125<sup>97</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2005 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered out 475 sxs 60/40 pozmix - 10% gel - 700# hulls.  
Squeezed 800' - 950' with 200 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2005 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1898'. Allied pumped 200 sxs 60/40 pozmix - 10% gel with 400# hulls - no circulation.  
Pulled tubing to 1500'. Allied pumped 110 sxs cement with 100# hulls.  
Pulled tubing to 800'. Allied pumped 120 sxs cement with 200# hulls - cwc.  
PTOH. Topped off with 10 sxs cement.  
Hooked up to 8 5/8". Allied pumped 25 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3846	3851		
3823	3827		
3810	3814		
3718	3721		
3709	3711		
3622			
3607			
3604			
3580			
3569			
3563			

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

102

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE

10-26-05

RECEIVED

OCT 26 2005

WTZ. NO.

2006060676

KCC WICHITA

OCT 24 2005

WAG:CES

SUNRAY OIL CORP #3 ORTH 2-14-20W  
NE SW SW

Contr. \_\_\_\_\_ ELLIS County

E 2255 Comm. 5-31-45 Comp. 6-27-45 IP 85 BOPD

Tops	Depth	Datum	Casing
ANH	1535		8" 1545
TOP	3234		5" 3868
HEEB	3492		
LANS	3556		SSO 3566
B/KC	3763 or 3783		3571-75: 3603-05: 3623-25
CONG	3845		2711-14: 3721-25
S SAND	3860		A/500
			Swb 3 BOPH/10 hr
ARB	3861		
TD	3876		

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

