

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20564-00-00
Spot: NWNENE Sec/Twnshp/Rge: 16-32S-4E
5014 feet from S Section Line, 1202 feet from E Section Line
Lease Name: YOULE Well #: 4
County: COWLEY Total Vertical Depth: 2690 feet

Operator License No.: 4699
Op Name: PHILLIPS OIL PROPERTIES INC.
Address: 1822 S. MEAD
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2689		50 SX CMT
SURF	8.625	200		125 SX CMT

43
87

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2005 11:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM Phone: (620) 438-2856

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/19/2005 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

8/5/2005 -- Bottom plug sanded back to 2570'; dump bail with 5 sacks of cement on top.
8/19/2005 -- Shot 5-1/2" casing at 1109'. POOH with 5-1/2" casing.
9/19/2005 -- RIH with tubing to 300'; circulated 105 sacks of 60/40 posmix with 3% gel to surface.
Braden Cement #05/504

Perfs:

Top	Bot	Thru	Comments
2627	2638		
RECEIVED KCC DISTRICT #2 OCT 10 2005 WICHITA, KS			

Remarks:

Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICAL)

INVOICED
DATE 10-19-05
INV. NO. 2006060645

RECEIVED
OCT 19 2005
KCC WICHITA