

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20703-00-00
Spot: S2NWSE Sec/Twnshp/Rge: 21-32S-8W
1650 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ROBINSON Well #: G-1
County: HARPER Total Vertical Depth: 3900 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3663		
PROD	4.5	3899	2800	200 SX CMT
SURF	8.625	267	0	250 SX CMT

#126⁷⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/26/2005 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN CLARKE Company: CLARKE CORPORATION Phone: (620) 886-5606

Proposed Plugging Method: SAND FROM 3663' TO 3584' PLACE 4 SX CMT. ON TOP W/BAILER. 35 SX @ 1325', 35 SX @ 800', CIRCULATE TO SURFACE @ 325'. USE 60/40 POZ W/4% GEL.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 05/10/2005 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CIBP was set at 3575' and capped with 3 sxs of cement. The casing was recovered from 2900'. Pulled casing to 1250' and pumped 35 sacks of cement. Pulled casing to 800' and pumped 35 sacks of cement. Pulled casing to 325' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #16581

Perfs:


Top	Bot	Thru	Comments
3680	3684		
3666	3676		
3634	3644		RECEIVED KCC DISTRICT #2 OCT 5 - 2005 WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED
OCT 13 2005
KCC WICHITA

INVOICED
DATE 10-13-05
INV. NO. 2006060619