

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-00493-00-01
Spot: NENESE Sec/Twnshp/Rge: 32-32S-4W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: WATKINS Well #: A1
County: SUMNER Total Vertical Depth: 3415 feet

Operator License No.: 5039
Op Name: AGV CORP.
Address: 123 N. MAIN
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2382		
CIBP		2554		
CIBP		3200		
CIBP		3245		
PROD	5.5	3395	0	300/200 SX CMT
SURF	10.75	178	0	

110 99

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/20/2005 10:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: KENT ROBERTS Company: AGV Phone: (620) 254-7222

Proposed Plugging Method: SAND BACK FROM 2382' TP 2240' & CAP W/2 SX CMT. RUN TUBING AND CIRCULATE CEMENT FROM 600' TO SURFACE. PORT COLLAR WAS CEMENTED FROM 321' TO SURFACE ON 9/17/2003 W/ 200 SX. (CIRCULATED 20 SX TO PIT).

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: NONE
Date/Time Plugging Completed: 09/20/2005 10:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 2240' and capped with 5 sacks of cement. No casing was recovered due to port collar at 321'. Tubing was ran to 600' inside of 5-1/2" casing. Cement was circulated to surface.
60/40 posmix with 4% gel
Allied Cementing #23178

Perfs:

Top	Bot	Thru	Comments
3252	3262		
3216	3222		
2570	2576		
2484	2490		
2292	2296		

RECEIVED
KCC DISTRICT #2
OCT 18 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

INVOICED
DATE 10-26-05
NO. 2006060665
Signed _____
(TECHNICIAN)

RECEIVED
OCT 26 2005
KCC WICHITA