

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-041-20094-00-00  
Spot: SENESW Sec/Twnshp/Rge: 29-14S-1E  
1657 feet from S Section Line, 3073 feet from E Section Line  
Lease Name: KOGLER Well #: A-1  
County: DICKINSON Total Vertical Depth: 2569 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2567		100 SX CMT
SURF	8.625	208		150 SX CMT

*\$ 83<sup>49</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2005 8:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: PAUL PACO Company: AMERICAN ENERGIES CORPORAT Phone: (620) 755-2246

Proposed Plugging Method: Sand to 50' above perfs and cap with 4 sxs cement. Set bridge at 250'. Dump slurry mix to fill from 250' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/23/2005 5:00 PM KCC Agent: GREG EVES

**Actual Plugging Report:**

Sanded to 2450' and capped with 4 sacks of cement. Pulled casing and set bridge at 250'.  
Dumped slurry mix to fill from 250' to surface.  
Total cement -- 120 sxs (6 yds of slurry mix); 20 sx/yd  
Smokey Valley #11985 & #12083

**Perfs:**

Top	Bot	Thru	Comments
2500			

**RECEIVED  
KCC DISTRICT #2  
OCT 17 2005  
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves

(TECHNICIAN)

**INVOICED**  
DATE 10-26-05  
INV. NO 2006060666

**RECEIVED**  
OCT 26 2005  
KCC WICHITA