

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05574-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 21-19S-9W
346 feet from S Section Line, 5048 feet from E Section Line
Lease Name: MEYERS Well #: 2
County: RICE Total Vertical Depth: 3209 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	147		
PROD	8.625	3150		
SURF	15	365		
SURF	12	1220		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2005 9:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: MARK HARMON Company: RESOURCE OPERATIONS, INC. Phone: (918) 446-6114

Proposed
Plugging
Method:

See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: PARTIAL
Date/Time Plugging Completed: 09/28/2005 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3175' and capped with 3 sacks of cement. Perforated at 1200' and 250'; already had holes in casing at 800' from 6" bit. Ran tubing to 3165' and spotted 20 sacks of cement. Pulled tubing to 1200' and pumped 50 sacks of cement. Pulled tubing to 790' and pumped 50 sacks of cement. Pulled tubing to 250' and circulated to surface.

60/40 posmix with 4% gel

Allied Cement #22532

Log Tech #15615

RECEIVED
KCC DISTRICT #2
OCT 3 - 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier

INVOICED

DATE

10-18-05

INV. NO.

2006060646

(TECHNICIAN)
RECEIVED

OCT 19 2005

KCC WICHITA