

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23408-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 13-26S-4E
4878 feet from S Section Line, 4850 feet from E Section Line
Lease Name: BLOIR A Well #: 29
County: BUTLER Total Vertical Depth: 2387 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2370		365-CMT CIRC
SURF	8.625	244		200 SX CEMENT

\$7758

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2005 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORTION Phone: (316) 682-1537

Proposed Plugging Method: 25 sxs on bottom @ 2350'; RIG @ 300'; circ cement to surf.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/21/2005 1:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Spotted 25 sacks of Class A cement at 2350'. Tagged plug at 2220'. RIH with tubing at 310'.
Established circulation; mixed and pumped 49 sacks of 60/40 posmix with 3% gel to surface.
Plugged down 1315'.

Cement circulated on backside 5-1/2" TD to surface in 1994.

United Cement #6533

Perfs:

Top	Bot	Thru	Comments
2370	2387		
2104	2112		
1980	1988		

RECEIVED
KCC DISTRICT #2
SEP 26 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

INVOICED

DATE 10-19-05

INV. NO. 2006060648

RECEIVED

OCT 19 2005

KCC WICHITA