

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14597-00-00

Spot: S2NENE

Sec/Twnshp/Rge: 18-20S-11W

990 feet from N Section Line,

660 feet from E Section Line

Lease Name: KOWALSKY

Well #: 3

County: BARTON

Total Vertical Depth: 3303 feet

Operator License No.: 4656

Op Name: DAVIS PETROLEUM, INC.

Address: RR 1, BOX 183 B

GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	5.5	3295	0	
------	-----	------	---	--

SURF	8.625	228	0	
------	-------	-----	---	--

33
#107

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/14/2005 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: DAVIS PETROLEUM, INC.

Phone: (620) 793-3051

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/14/2005 2:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 550' and 1350'.
Ran tubing to 2000'.
Pressured backside to 750# P.S.I. - had cement in nipple.
Circulated 5 1/2" with 350 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
POOH. Pumped 50 sxs cement down casing.
Max. P.S.I. 400#. S.I.P. 250#.

Remarks: COPELAND CEMENT & ACID, INC.

Plugged through: TBG

District: 04

Signed Case Morris

(TECHNICIAN)

INVOICED

DATE

10-26-05

INV. NO.

2006060669

RECEIVED

OCT 26 2005

KCC WICHITA

Form CP-2/3

OCT 20 2005