

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05068-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 29-11S-17W
4620 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GLATHART Well #: 5
County: ELLIS Total Vertical Depth: 3648 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3624	0	
SURF	8.625	1315	0	

H-118^{SB}

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2005 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 700# hulls.
Casing leak squeezed - 2730' w/300 sxs.
2 7/8" tubing stuck at 3570'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2005 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 50 sxs 60/40 pozmix - 10% gel neat, followed with 235 sxs cement and 700# hulls - circulated out 8 5/8" x 4 1/2" casing.
Shut in. Max. P.S.I. 500#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3624	3648	OH	
3592	3600	OH	

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 10-26-05

WV. NO. 2006060676

RECEIVED

OCT 26 2005

KCC WICHITA

Form CP-2/3

OCT 20 2005