

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21141-00-00
Spot: E2 Sec/Twnshp/Rge: 28-9S-29W
2640 feet from S Section Line, 1470 feet from E Section Line
Lease Name: SCHWARZ AND PRATT Well #: 1
County: SHERIDAN Total Vertical Depth: 4280 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: RR 2, BOX 14
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	275		

#139¹⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/14/2005 1:00 AM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARRELL ANDERSON Company: NOR-WEST KANSAS OIL, LLC Phone: (785) 421-6266

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES Witness Type: NONE
Date/Time Plugging Completed: 10/14/2005 1:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 2500' w/25 sxs.
2nd. Plug at 1320' w/100 sxs.
3rd. Plug at 337' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

INVOICED

DATE 10-26-05

TRK. NO. 2006060677

RECEIVED

OCT 26 2005

KCC WICHITA

Form CP-2/3

OCT 24 2005