

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22639-00-00
Spot: NWSE Sec/Twnshp/Rge: 27-30S-13W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HARTLEY Well #: 1
County: BARBER Total Vertical Depth: 4770 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: 155 N. MARKET - SUITE 800 PO BOX 4
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3800		WITH 2 SX CMT
PROD	4.5	4100	2670	WITH 150 SX CMT
SURF	10.75	261		WITH 220 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/13/2005 1:30 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 3810' WITH 2 SX CMT. PLUG AT 630' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2005 2:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3800' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
PLUG THROUGH 4 1/2" CASING. 1ST PLUG AT 630' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 290' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3858	3863		2 SHOTS PER FT.

RECEIVED
OCT 24 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 10-25-05
INV. NO. 2006060663

Form 08-24