

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-041-20093-00-00
Spot: SENWSE Sec/Twnshp/Rge: 29-14S-1E
1693 feet from S Section Line, 1746 feet from E Section Line
Lease Name: ARVIN EILDERS Well #: 4
County: DICKINSON Total Vertical Depth: 2571 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2569		100 SX CMT
SURF	8.625	210		150 SX CMT

\$8354

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2005 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 755-2246

Proposed Plugging Method: Sand to 50' above top perms and cap with 4 sxs cement. Set bridge at 250' and fill with slurry mix from 250' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 09/14/2005 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2490' and capped with 4 sacks of cement. Pulled casing and bailed fluids to 250'. Set bridge and dumped slurry mix to fill from 250' to surface.

Total cement -- 120 sxs (6 yds slurry mix); 20 sx/yd

Smokey Valley #11970

Perfs:

Top	Bot	Thru	Comments
2545	2547		

RECEIVED
KCC DISTRICT #2
OCT 17 2005
WICHITA, KS

Remarks:
Plugged through: CSG

District: 02 Signed Greg Eves (TECHNICIAN)
INVOICED **RECEIVED**
DATE 10-26-05 OCT 26 2005
INV. NO. 2006060606 **KCC WICHITA**

Form CP-2/3