

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20922-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 19-18S-9W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: BOLDT A Well #: 1  
County: RICE Total Vertical Depth: 3228 feet

Operator License No.: 3682  
Op Name: CONNELL, MARK ALLEN  
Address: 606 W ALBRO  
CLAFLIN, KS 67525

| String | Size  | Depth (ft) | Pulled (ft) | Comment       |
|--------|-------|------------|-------------|---------------|
| PROD   | 5.5   | 3221       | 1685        | 100 SX CEMENT |
| SURF   | 8.625 | 230        |             | 200 SX CEMENT |

91  
\$104

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2005 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/07/2005 12:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3170' and capped with 5 sacks of cement. Cut off 5-1/2" casing at 1687'. Pulled casing to 1200' and pumped 35 sacks of cement. Pulled casing to 850' and pumped 35 sacks of cement. Pulled casing to 280' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #17975

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3221 | 3228 | OH   |          |

**RECEIVED  
KCC DISTRICT #2  
OCT 11 2005  
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

**INVOICED**

DATE 10-26-05  
REF. NO. 2006010667

RECEIVED

OCT 26 2005

KCC WICHITA