

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22457-00-00  
Spot: E2NENW Sec/Twnshp/Rge: 2-35S-1E  
660 feet from N Section Line, 2970 feet from E Section Line  
Lease Name: AUSTIN Well #: 1-2  
County: SUMNER Total Vertical Depth: 3802 feet

Operator License No.: 30253  
Op Name: CYCLONE PETROLEUM, INCORPORAT  
Address: 7030-C S. LEWIS ST., STE 541  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		

#12357

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2005 7:00 PM  
Plug Co. License No.: 32854 Plug Co. Name: GULICK DRILLING CO., INC.  
Proposal Revd. from: RON GULICK Company: GULICK DRILLING CO., INC. Phone: (620) 583-3066

Proposed Plugging Method: 35 sxs 312'; 25 sxs 60'; 15 sxs in rathole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE  
Date/Time Plugging Completed: 10/07/2005 8:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The drill pipe was ran open-ended to 312' and spotted 35 sxs of cement. The drill pipe was pulled to 60' and 25 sxs of cement circulated to surface. The rathole was circulated with 15 sacks of cement.

60/40 posmix with 4% gel

Consolidated Cement #7695


RECEIVED  
KCC DISTRICT #2  
OCT 17 2005  
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

INVOICED

DATE 10-26-05  
INV. NO 2006060668

Form CP-2/3

RECEIVED  
OCT 26 2005  
KCC WICHITA