

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-181-20224-00-00

LEASE NAME Albert McMichael

WELL NUMBER #1-12

SPOT LOCATION 150' W-SE-NW

SEC. 12 TWP. 6 RGE. 37 ^{KCC of} (E) of (W)

COUNTY Sherman

Date Well Completed 6/16/82

Plugging Commenced 4/24/86

Plugging Completed 4/24/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300 Wichita, Ks 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, KS

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Marmaton Depth to top 4610 bottom 4680 T.D. 5031

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil & SW	4610	4680	8 5/8	340	0
				4 1/2	5030	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 35 sx cotton seed hulls followed by 150 sx 65-35 Poz w/10% gel, 2% Econolite & 1 sx hulls dwn csg. Yield @ 3.63 cu. ft/sx for total of 544 cu. ft. Volume of csg = 446 cu. ft. Max press = 400 psig. SIP = 200 psig. Pumped 1 sx hulls dwn annulus followed by 50 sx 65-35 Poz w/10% gel, 2% Econolite. Max press = 200 psig. SIP = 175 psig.
Witnessed by Mr. Carl Goodrow


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 N. Water, Suite 300 Wichita, Ks 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

L.O. Butner, Western Div., Prod. Mgr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: L.O. Butner
(Address) 250 N. Water, Suite 300; Wichita



SUBSCRIBED AND SWORN TO before me this 30 day of April, 1986

Kerran Redington
Notary Public
Kerran Redington

My Commission expires: 2/6/90

STATE CORPORATION COMMISSION
MAY 01 1986
CONSERVATION DIVISION
Wichita, Kansas
5-1-86