

Original-State Corp. Comm.
 Copy-B. A. Conner-357 FPB
 Copy-Mary Crump-OK City
 Copy-Well File

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION CP-4
 Rev. 12-15-80
 DEC 16 1982
 12-16-82
 CONSERVATION DIVISION
 Wichita, Kansas

WELL PLUGGING RECORD

18-181-20228-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Sherman SEC. 10 TWP. 6 RGE. 37 E/W
 Location as in quarters or footage from lines:
 660' FSL & 660' FEL NE/4

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate Well
 correctly on above
 Section Platt.

Lease Owner Phillips Petroleum Company
 Lease Name Llanos Well No. 7
 Office Address Box 287, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed August 19, 1982
 Application for plugging filed August 20, 1982
 Plugging commenced December 9, 1982
 Plugging completed December 15, 1982
 Reason for abandonment of well or producing formation
Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrown
 Producing formation Dry Depth to top ---- bottom ---- T.D. 3734'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|------------|-------------|------|-------|--------|--------|------------|
| Surface | Water | 0' | 419' | 8 5/8" | 419' | -0- |
| Production | Oil & Water | 0' | 4999' | 5 1/2" | 4999' | 2368.06' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set. MIRU Ostrom Well Service & pulled stress on csg.
RU Dialog - found free point @ 2367'. Shot csg off @ 2367'. Pulled 25 jts 5 1/2"
15.5# csg (985.92'). Pulled 35 jts 5 1/2" csg (1382.14'). Removed csg head.
Installed swage & valve. Conn. Hallib to 8 5/8" csg. Pumped 4 sx hulls, 80 sx 50-50
Pozmix w/6% gel & 3% CaCl, 40 sx gel, 8 5/8" wiper plug; 70 sx 50-50 Pozmix w/6% gel
& 3% CaCl @ 3 BPM @ 450 PSI. ISIP - 250 PSI. To weld plate on 8 5/8" csg. Well
Plugged & Abandoned, 12-15-82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dialog Company
Great Bend, Kansas


STATE OF Kansas COUNTY OF Barton, ss.

J. R. Miller (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) J.R. Miller
Box 287, Great Bend, KS 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 82

Velma L. Mogg
 Notary Public.



My Commission expires: February 15, 1984