

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21,609-0000

LEASE NAME Reichard Byfield

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

535 Ft. from N Section Line

2490 Ft. from E Section Line

SEC. 19 TWP. 7S RGE. 17 (E) or (W)

LEASE OPERATOR Damson Oil Corporation

ADDRESS 3300 N "A" Bldg 8, Suite 100 Midland, TX 79705

COUNTY Rooks

PHONE# (915) 687-0455 OPERATORS LICENSE NO. 08098

Date Well Completed 4-4-82

Character of Well oil

Plugging Commenced 4-6-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-10-89

The plugging proposal was approved on 1-24-89 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3258 Bottom 3264 T.D. 3315
PBDT 3292

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle		3258	3264	13-3/8"	92'	
				8-5/8"	1185'	
				5-1/2"	3315'	
				2-7/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mx & pmp 260 sx 60/40 Pozmix cmt w/6% gel w/300# Cottonseed hulls 1st 20 bbls slurry down
5-1/2" csg w/perfs @ 3258-3264', pmpd @ 4 BPM @ 500 psi avg. Mx & pmp 40 sx Common cmt
w/additives behind Pozmix cmt @ 2 BPM @ 500 psi. Mx 10 sx Portland cmt & fill all strings
4" below GL, weld on name plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address PO Box 428 Hayes, KS 67601

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Damson Oil Corporation

STATE OF Texas COUNTY OF Midland, ss.

JUL 17 1989
7-17-89
CONSERVATION DIVISION
Wichita, Kansas

Don R. Craig (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don R Craig
3300 N "A" Bldg 8, Suite 100
(Address) Midland, TX 79705

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 89

Jackie Barrett Jackie Barrett
Notary Public

My Commission Expires: 12-31-89