

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-21,487-0000

LEASE NAME Hutton

WELL NUMBER A1

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR APACHE CORPORATION SWSW SEC. 19 TWP. 7S RGE. 17 ~~NE~~ or (W)

ADDRESS 1700 Lincoln, Ste. 1900, Denver, CO 80217 COUNTY Rooks

PHONE# (303) 837-5000 OPERATORS LICENSE NO. 8932 Date Well Completed 11/17/81

Character of Well Oil Plugging Commenced 8/19/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 8/19/88

The plugging proposal was approved on August 12, 1988 (verbal) (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3231.5' Bottom 3255' T.D. 3255'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1127'	N/A
				5 1/2"	3231.5'	N/A

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Dug out wellhead and hooked up Allied Cementing truck to 8-5/8" casing. Pressured to 600#, held O.K. Released packer. Hooked up to 5-1/2" casing. Pumped 300# cotton-seed hulls followed with 300 sxs 60/40 pozmix with 8% gel. Pumped down 5-1/2" casing. Maximum pressure was 1000#. ISIP 900#. (If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Allied Cementing License No. N/A

Address Box 31, Russell, Kansas 67665



NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: APACHE CORPORATION

STATE OF Colorado COUNTY OF Denver, ss.

SEP - 1 1988  
9-1-88

Paul Noble (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul R Noble

(Address) Same as above

SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 88

My Commission Expires: 12/26/88  
Notary Public  
Carolyn D. Hepp

Cut off 8 5/8" and 5 1/2" casing. Welded cap over casing and dated. Levelled location with dozer.