

API NUMBER 15-163-21,356
 LEASE NAME F. WALKER
 WELL NUMBER 1
330 Ft. from S Section Line
2970 Ft. from E Section Line
 SEC. 19 TWP. 7S RGE. 17 (E) or (W)
 COUNTY ROOKS
 Date Well Completed 7/12/81
 Plugging Commenced 10/18/91
 Plugging Completed 10/18/91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR FREMONT ENERGY CORPORATION
3030 N.W. EXPRESSWAY, SUITE 1602
 ADDRESS OKLAHOMA CITY, OKLAHOMA 73112
 PHONE# (405) 943-4581 OPERATORS LICENSE NO. 30571

Character of Well OIL
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/15/91 (date)
 by GILBERT C. SCHECK (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? YES

Producing Formation ARBUCKLE Depth to Top 3224' Bottom T.D. 3256'
 Show depth and thickness of all water, oil and gas formations.

11-19-91
 RECEIVED
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
SURFACE CSG		0	1015'	8 5/8"	7/7/81	NO
ARBUCKLE	OIL	0	3226'	5 1/2"	7/12/81	NO

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
FILLED 5 1/2" CSG WITH 235 SKS OF 65/35 POS CEMENT W/10% GEL AND 5 SKS OF HULLS MAX PRESSURE 1000# TSTP 800#. FILLED 8 5/8" CSG WITH 200 SKS OF 65/35 POS CEMENT WITH 10% GEL AND 1 SK OF HULLS MAX. PRESSURE 1200# TSTP 400# CUT CASINGS OFF SET BELOW GROUND LEVEL. CEMENT WAS AT SURFACE
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING CO INC. License No. _____
 Address PO. BOX 31 RUSSELL, KANSAS 67665
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: FREMONT ENERGY CORPORATION
 STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

ROLAND NYP (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that he same are true and correct, so help me God.

(Signature) Roland Nyp
 (Address) Box 213 STOCKTON, KS 67669

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 91
Denise M. Murchie
 Notary Public
 My Commission Expires: 7-17-94