

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202-1286

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21,843-00-00

LEASE NAME DWJ

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #2
990 SW NE NW
330 Ft. from S ~~SECTION~~ Line &
W
330 Ft. from E ~~SECTION~~ Line
1700 of NW 1/4
SEC. 19 TWP. 7S RGE. 17 (E) or (W)

LEASE OPERATOR Apache Corporation 80203
ADDRESS 1700 Lincoln St., Suite 4900, Denver, CO COUNTY Rooks

PHONE# (303) 831-6500 OPERATORS LICENSE NO. 8932 Date Well Completed 11-1-82

Character of Well Temporarily Abandoned Plugging Commenced 9/21/84

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 9/21/84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Distric Office in Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3284' Bottom 3330' T.D. 3330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil Shows	Surf	88	13 3/8	88'	None
Arbuckle	Oil Shows	Surf	1319	8 5/8	1319	None
		Surf	3364	5 1/2	3364	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU Sun Oilwell Cementers (no rig was used to plug with). Started pumping down 5 1/2" O.D. casing with 40 sacks 50/50 Poz cement with 8% gel and 2 sx cotton, seed hulls, followed with 16 sacks of gel spacer, followed by a wooden plug with rubber cups, finished with 85 sacks of 50/50 Poz cement. STP 650#. Cemented 8-5/8" O.D. casing as follows: Pumped 225 sacks of 50/50 (over)

(If additional description is necessary, use BACK of this form.)

Number not required for service companies

Name of Plugging Contractor Sun Oilwell Cementers License No. _____

Address Box 69, Hays Kansas

STATE OF Colorado COUNTY OF Denver, ss.

Raymond C. Kersey (Employee of Operator) or (Operator) of above-described well, being first/duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Raymond C. Kersey

(Address) One United Bank Center
1700 Lincoln St., Ste. 4800

11-5-84

SUBSCRIBED AND SWORN TO before me this 1 day of November, 19 84

Julie [Signature]
Notary Public

My Commission Expires: 11/5/84

1700 Lincoln St
Denver CO 80203

Poz cement with 8% gel and 2 sacks of gel spacer SIP was 650#. Cut 5½" and 8 5/8" casing 4 feet below ground level. Weld steel cap over casing. Backfilled and covered casing. Cementing operations were witnessed by Dennis Hamel and Dal Bathazor with the Kansas State Corporation Commission.