

RECEIVED

OCT 31 2005

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

3846-51, 3823-27, 3810-14 Depth to Top: _____ Bottom: _____ T.D. _____

3718-21, 3709-11, 3622, 3607 Depth to Top: _____ Bottom: _____ T.D. _____

3604, 3580, 3569, 3563 Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-03096-00-00

Lease Name: Orth

Well Number: #3

Spot Location (QQQQ): NE - SW - SW -

990 Feet from North / South Section Line

4290 Feet from East / West Section Line

Sec. 2 Twp. 14 S. R. 20 East West

County: Ellis

Date Well Completed: 6/45

Plugging Commenced: 10/18/05

Plugging Completed: 10/18/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	1555	8 5/8	1555	0
	Production	Surface	3861	5 1/2	3861	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Allied set up to plug with 465 sx 60/40 poz, 10% gel, 700# hulls. Pumped 200 sx & 400 hulls at 1886' pulled tbg to 1550'
pumped 110 sx & 100# hulls, pulled tbg to 800' pumped 120 sx & 200# hulls cement circulated. TOH w/ tbg,
topped casing off with 10 sx. Hookup to 8 5/8", pumped 25 sx to 500#. SI. Witnessed by Rich Williams w/KCC.


Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 28th day of October, 20 05

Susan Brady My Commission Expires: 11-4-07
Notary Public