

STATE OF KANSAS
STATE CORPORATION COMMISSION
200, Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,163,21,739 ^{00 00}

LEASE NAME DWJ

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

330 Ft. from N Section Line

330 Ft. from E Section Line

LEASE OPERATOR Apache Corporation

SEC. 19 TWP. 7S RGE. 17 (X) or (W)

ADDRESS 1700 Lincoln Street, Denver, CO

COUNTY, Rooks

PHONE#(303) 837-5000 OPERATORS LICENSE NO. 8932

Date Well Completed 8/8/82

Character of Well Oil

Plugging Commenced 12/19/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/20/88

The plugging proposal was approved on December 14, 1988 (date)

by Dale Balazor (verbal) (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3246 Bottom 3286' T.D. 3315'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	98'	
				5-1/2"	1224'	

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1989
1-25-89
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dug out wellhead. Run wireline to 1700' in 5 1/2" casing. POOH. Hooked up. Allied Cementing pump truck to 5 1/2" casing. Pumped 200# cotton seed hulls, followed with 220 sxs 60/40 pozmix, 6% gel. Pumped additional 200# cotton seed hulls in first 50 sxs cement. Total of 400# hulls. Pressured to 1500 psi (over) (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. --

Address 24 South Lincoln, Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Apache Corporation

STATE OF Colorado COUNTY OF Denver, ss.

Paul Noble (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul R Noble

(Address) 1700 Lincoln, Ste. 1900, Denver

SUBSCRIBED AND SWORN TO before me this 9th day of January, 19 89

My Commission Expires: 11/3/93
Carolyn D. Dean
Notary Public

Held O.K. Unhooked cement truck. 8 5/8" casing was squeezed in 11/86 and cemented to surface. Cut off wellhead and capped. Dug out flowline below ground level. Dozer leveled location and bury junk gas line.

Surface owner will assume all responsibility for restoration work on the battery site.