

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21,713-00-00

LEASE NAME Liebenau

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 6

4950 Ft. from S Section LI

1650 Ft. from E Section LI

SEC. 19 TWP. 4s RGE. 17 W (E) or (

COUNTY Rooks

Date Well Completed 8-30-82

Plugging Commenced 11-5-90

Plugging Completed 11-5-90

LEASE OPERATOR Helmerich & Payne, Inc

ADDRESS Box 558, Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3351 Bottom 3357 T.D. 3312

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil-water	3351	57	8-5/8	1209	0
				5-1/2	3302	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each set.

Perforate 5 1/2, 800' F.S. Pumped 75 sks 65/35, 8% Gel, 1/4# Floseal, then pump 200# hulls
Pumped hulls to 800' F.S. Open 8-5/8 circulated cmt to surface. Close in pressure 600#
Pump total 225 sks 65/35, 200# hulls

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Kansas

STATE OF Kansas COUNTY OF Rooks, ss.

Millard L Lindsay (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
statements, and matters herein contained and the log of the above-described well as filed th
the same are true and correct, so help me God.

(Signature) Millard Lindsay

(Address) Box 558, Garden City, KS 67846

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1990

RECEIVED
STATE CORPORATION COMMISSION

11-15-90

My Commission Expires: August 15, 1992

Notary NOV 15 1990

CONSERVATION DIVISION
Wichita, Kansas

Form C

Revised 08