

4-24

4-032226

00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-193-20,319

C SE NW /4 SEC. 13, 06, 36 W  
3300 feet from S section line  
3300 feet from E section line

Operator license# 5088

Lease: Miller B Well # 2

Operator: John J. Darrah Jr.

County: Thomas 158.02

Address: 225 N. Market - #300  
Wichita, Kansas 67202

Well total depth 4862 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 432 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 24 Month: April Year: 1997

Plugging proposal received from: Phil Martin

Company: John J. Darrah Jr. Phone: -

Were: Order 365 sxs 60/40 pozmix - 10% gel - 500# hulls - 18 sxs gel.

RECEIVED  
KANSAS CORPORATION  
MAY 11 AM 11:55  
5-1-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:20 A.M., Day: 24 Month: April Year: 1997

Actual plugging report: 8 5/8" set at 432' w/300 sxs. 5 1/2" set at 4862' w/200 sxs.  
Prod Perfs 4521' - 4525'. Squeezed at 1144' - 1170' with 300 sxs. Critical control shots  
at 2000' and 3000'. Squeezed 5 1/2" with 50 sxs cement blend with 200# hulls followed with  
18 sxs gel, followed by 180 sxs cement blend with 300# hulls to Max. P.S.I. 500#. Close in  
P.S.I. 100#. Squeezed 8 5/8" with 50 sxs cement with 150# hulls to Max. P.S.I. 500#. Close  
in P.S.I. 300#. Plug complete.

Remarks: Dakota 1794' - 2094'. Anhy. 2974' - 3014'.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  and  observe the plugging.

Carl Goodrow  
(agent)

INVOICED  
DATE MAY 02 1997  
INV. NO. 48045  
4-24 JUL 11 1997