

6-050099

1-19

128 ION R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,184-0002

C NE NW /4 SEC. 13, 6 S, 36 W
4620 feet from S section line
3300 feet from E section line

CO. REGISTRATION DIVISION
WICHITA, KANSAS
1993

Operator license# 5088

Lease Miller B well # 1

Operator: John Jay Darrah

County Thomas

Address: 412 East Douglas
Wichita, Kansas

Well total depth 4840 feet ^{157.30}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 400 feet

Aband. oil well , Gas well , Input well , SWD XX, D & A

Plugging contractor: John Jay Darrah License#

Address: As above

Company to plug at: Hour: P. M. Day: 19 Month: January Year: 1993

Plugging proposal received from: Phil Martin

Company: Contract Pumper phone:

Were: 5 1/2" casing set at 4840'. PBSD at 4800'. Perfs from
4521'to 4525'. Order out 50 sx common, 300 sx 60/40 poz, 8% gel,
20 sx bentonite gel.

Plugging Proposal Received by: Phil Martin
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 6:50 PM, Day: 19, Month: January, Year: 1993

Actual plugging report: Ran tubing to 4590'. Pump in 50 sx common cmt.
Pull 3 jnts, pump 10 sx gel. Pull 32 jnts tubing to 3410, pump 100 sx
60/40 poz, 8% gel. Pull 32 jnts tubing to 2410', pump 10 sx gel.
Pull 32 jnts tubing to 1410', pump 60 sx 60/40 poz, 8% gel. Pull 22 jnts
to 710', pump 60 sx 60/40 poz, 8% gel. Cement circulated. Pump 75 sx
down backside, 350# shut in pressure.

Remarks: Allied on plugging. This plugging approved by Don Butcher

I did [] did not [] observe the plugging.

Bruce D. Basye

Bruce D. Basye
(agent)
Form CP-2/3

INVOICED

DATE 2-18-93

INV. NO. 37380

1-19 MAR 24 1993 MAY 11 1993