

7-9 15-193-00002-00-01

To: 031385  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C SW NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1978  
SEC. 6 T 6 S. R 36 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131  
Operator: Thunderbird Drilling  
Name & Address: Box 97  
Ellinwood, Ks. 67530

3300 feet from S section line  
4620 feet from E section line  
Lease Name Briney Well # 1  
County Thomas 157.95  
Well Total Depth 4860 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pulling License Number \_\_\_\_\_  
Address Great Bend, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 9 Month: July Year: 19 90

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing (phone) \_\_\_\_\_

were: 8 5/8 set at \_\_\_\_\_ w/ \_\_\_\_\_ sks cwc. 4 1/2 set at 4790 w/100 sks. PBD 4697.

Perfs 4672-82. Order sand common cement. Pull pipe. Order 250 sks 65/35 poz

8% gel 500 lbs. hulls. Allied Cement Co. Hensley Water Trucks  
Hole open.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00PM Day: 9 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom to 4620 w/4 sks common cement on sand w/bailer.

Recovered 1563 of casing.  
Sq 8 5/8 w/250 sks cement blend with 500 lbs. hulls.

Mixed into max psi 300 lbs. Close in psi 150 lbs.

Plug complete.

Remarks: \_\_\_\_\_  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE 7-26-90  
INV. NO. 28738

Gib.S.

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
JUL 17 1990  
7-17-90