

6030038

193-20,233-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

SUNWSE Sec. 6, T 6 S, R 36 W E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name DULL Well # 2-6

Operator: MURFIN DRUG CO.  
Name & Address 617 UNION CENTER  
WICHITA, KANSAS 67202

County THOMAS

Well Total Depth 5024 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING license Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 2 Month: 11 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO GENE SMITH

(company name) KELSO (phone) \_\_\_\_\_

were: BOTTOM PLUG - 4SX CEM. ON BOTTOM - SAND TO 60' ABOVE

PERF'S - 4SX. CEM. ON TOP.

TOP PLUG - PUMP DOWN 8 5/8 WITH 2SX HULLS - 4SX. GEL.

100SX CEM. MIX. - 36SX. GEL. - 8 5/8 PLUG 70SX CEM MIX.

50/50 p 2 6 2 GEL 3 2 cc

Signed Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 PM Day: 2 Month: 11 Year: 19 83

ACTUAL PLUGGING REPORT BOTTOM PLUG AS ABOVE -

Top plug - Pumped down 2SX HULLS - 4SX. GEL 100SX.

CEM MIX. 6SX. GEL BLEW OUT 8 5/8 COLLAR AND PIPE - CALLED

WELDER - PIPE WORE SO BAD WELDS WOULDNT HOLD SUCKED OUT

20' OF GEL AND PLACED CEM MIX. TO 6' BELOW SURFACE

AFTER 3 HOURS SHUT DOWN FOR WELDER CEMENT & GEL IN HOLE SET UP AND COULDNT BE MOVED IN HOLE WITH PUMP - PRESSURE HIT 500# AND COLLAR AND CASING RUPTURED

Remarks: THIS WELL IS IN AREA OUTSIDE OF AREA TO BE PROTECTED.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe plugging.

INVOICED  
DATE 11-28-83  
INV. NO. 7039-W

RECEIVED  
NOV 7 1983  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)