

6 070307

API NUMBER 15-163-22-690-00-00 *R-00*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

*NW-3W-5E*, SEC. 13, T. 7 S, R 20 *W*  
990 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6111  
Operator: N-B Company Inc.  
Name & Address: P.O. Box 506  
Russell, Kans. 67665

Lease Name Stice Well # 1  
County Rooks 115.70  
Well Total Depth 3560 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated # 1AC

Plugging Contractor Emphasis Oil Operations License Number 8241  
Address P.O. Box 506 Russell, Kans. 67665

Company to plug at: Hour: 10:00 PM Day: 5<sup>th</sup> Month: JUNE Year: 19 85

Plugging proposal received from Nick Kneutzer

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: 8 5/8" 251' ET SR. cnc #160 SK 60 3% 2% 140 Pozmix Gel-Ca-Cl. (By Allied Cont,  
Order 210 SK 50 6% 3% 1 SK Cells  
140 Pozmix Gel-Ca-Cl. - 1 Flake end 8 5/8" Plug

Spot with Drill stem, Recondition Hole (45 vis) Heavy Mud Between All Plugs  
Mud Condition 9.5 weight, Vis. 46, No Circulation Problems.

EV. 2020 Amhy. 1553 Tabacille 3480

RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas  
JUN 24 1985  
JUN 24 1985  
Plugging Proposal received by Jefferson Schmitt  
Doie (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 8:00 PM Day: 6<sup>th</sup> June Year: 19 85

ACTUAL PLUGGING REPORT Ordered 210 SK 50 6% 3% 1 SK Cells  
140 Pozmix Gel-Ca-Cl. - 1 Flake + 8 5/8" Plug

Spotted with Drill stems - Reconditioned hole - Heavy Mud Between All Plugs  
1<sup>st</sup> Plug @ 3420 FT #25 SK CNT, 2<sup>ND</sup> Plug @ 1560 FT #25 SK CNT,  
3<sup>RD</sup> Plug @ 920 FT #100 SK + 1 SK Cells, 4<sup>TH</sup> Plug @ 270 FT #40 CNT,  
5<sup>TH</sup> Plug Solid Bridge Hall's Plug @ 40 FT #0 #10 SK CNT, 10 IN Rat Hole (circumfer)  
Cemented By Allied Cont

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-26-85  
INV. NO. 8736

Signed Jefferson Schmitt  
(TECHNICIAN) 6-21-85